

LINNIX EDUCATION MAINTENANCE PROJECT

CIVIL & TECHNICAL DIVISION

CAMPANY
 CONTACT
 ADDRESS

EMAIL ADDRESS
 PHONE #
 DATE

INSTRUCTION:

State the company name with all required information above Fill in the material price and in the highlighted column Double check the quote prior submission, Cotact this email address for further enquiries : civilandtechnical@mlpid.gov.ki

Serial No	Description	TOTAL OF QUANTIES	Unit	PRICE	TOTAL
1.0	CONCRETE WORK				
	Portland Cement 40Kg	1188	bags		
3.0	REINFORCEMENT WORK				
	Reinforced rod D12mm Ø minimum Grade 300MPa	377	lengths		
	Reinforced rod D10mm Ø minimum Grade 300MPa	46	lengths		
	R6 diam bar for stirrups minimum Grade 300MPa	107	lengths		
	665 BRC Mesh reinforcement 6mx2.4m minimum Grade 300MPa	35	sheet		
	Polythene black plastic 1.8x60mx4mm	9	roll		
	Tie/Bind Wire (20m length)	26	spools		
4.0	CARPENTRY				
	Radiata Pine 200x50mm x6m F7 Grade, seasoned pine	22	length		
	Radiata Pine 100x50mm x6m F7 Grade, seasoned pine	103	length		
	Radiata Pine 200X25mm x6m F7 Grade, seasoned pine	84	length		
	Radiata Pine 150X25mm x6m F7 Grade, seasoned pine	25	length		
	Radiata Pine 75X50mm x6m F7 Grade, seasoned pine	449	length		
	Radiata Pine 50X50mm x6m F7 Grade, seasoned pine	412	length		
	Construction plywood 2.4x1.2mx6mm	159	Sheets		
	Exterior plywood 2.4mx1.2m x20mm	20	Sheets		
	Hardboard 2.4x1.2x6mm	69	Sheets		
	Cement board (2.4x1.2mmx6mm)	9	Sheets		
	Angle iron bracket	15	nos		

	Anchor bolt&nut M12@200mm		100	nos		
	PC - Concrete two - part epoxy adhesive (8.6oz)		5	nos		
	Galv pipe 50mm x 6m		8	nos		
	Builders Strapping (25mmx27m)		6	length		
	5.0 ROOFING COVERING					
	Roof Sheet 8ft ,'Bluescope Lysaght': Colorbond ULTRA		218	sheets		
	Roof Sheet 15ft ,'Bluescope Lysaght': Colorbond ULTRA		481	sheets		
	Roof Sheet 12ft ,'Bluescope Lysaght': Colorbond ULTRA		89	sheets		
	Chicken wire 20mm x 1.25m		40	roll		
	Standard Ridge cap 2.4m length		62	length		
	Sisalation		20	roll		
	Gutter (aluminium with U shape) 2.4m		7	length		
	Standard Flashing edge 2.4m length		19	length		
	6.0 JOINERY WORK					
	Galvanise mesh window 2.4x1.2m		156	sheets		
	Fly insect screen 30x0.912m		50	roll		
	Panel door 1981x890mm		20	no		
	Wire mesh rolls 40x40mmx15m		15	no		
	Hollow core flush single door 2000x890x40 thick		30	no		
	Stainless butt hinges 100mm x 75mm		150	pairs		
	Butt hinges 4 inches		68	no		
	Entrance Lock set		8	no		
	Entrance/barrel lock		64	no		
	Padlock 4 inches		16	no		
	Lockable pad bolt zinc - plate 100mm		16	pkt		
	Barrel bolt 100mm		126	pairs		
	Stainless Dynabolt 12mmdia X 100mm		205	no		
	Louver glass 610mm		70	nos		
	Louver glass 510mm		1715	nos		
	Louver frame 8 blade with screws		458	pairs		
	Louvre glass 152x710mm		405	no		
	Oil Putty		5	pairs		
	Silicon seal for finishing		5	no		
	<i>Caulking gun</i>		1	no		
	Louver glass 710mm		1883	no		
	Clear Varnish 4ltrs		2	no		
	Black Wood Stain 4ltrs		2	tins		
	Dap 18001 Kwik-Seal		5	tube		

	Anchoring Epoxy		5	tube		
	Wood Sand Paper Rough		20	m		
	Wood Sand Paper Smooth		20	m		
	Wood Sand Paper 160 grit		100	length		
	Wood Sand Paper 220 grit		20	tenths		
	Screw 150mm		57	pieces		
7.0	TILING WORK					
	Vinyl tile 300x300mm		12406	tiles		
	Vinyl Adhesive 4ltr tin		166	tins		
8.0	PAINTING WORK					
	Interior/Exterior Multi-Surface Primer, Sealer, and Stain Blocker 10ltrs		32	bucket		
	Arcylic primer undercoat 10ltrs-white		66	bucket		
	Pink Primer 4ltr		22	tins		
	Undercoat 4ltr		21	tins		
	Enamel coat paint 4ltr -C-White		129	tins		
	Paint for rust		12	tins		
	roller brush & tray		36	nos		
	Brush 100mm		66	nos		
	Skin for roller brush		100	nos		
	Roller handle 100mm		13	nos		
9.0	NAILING WORK					
	Galvanise Nail 4"		148	kg		
	Galvanise Nail 3"		107	kg		
	Galvanise Nail 2"		38	kg		
	Grount Nail 1 1/2"		33	kg		
	Grount Nail 2"		49	kg		
	Metal roof screw nail 3"		4216	kg		
	Grout Nail 1"		20	kg		
	Concrete Nail 2"		5	kg		
	Concrete Nail 3"		3	kg		
	Concrete Nail 4"		8	kg		
	U-Nail 1-1/2"		12	kg		
	Gang Nail		62	nos		
	Roofing Nail 3"		84	kg		
	Stable gun		1	no		
	Stable gun nails/stables		5	kg		

10.0	ELECTRICAL & IT WORK					
	Battery		3	no		
	Controller		3	no		
	Led lights		27	no		
	Cable 1.5mm2		150	m		
	GRAND TOTAL CEILING COST					
	TOTAL OF MATERIALS					
11.0	SHIPMENT COSTS					
	Preliminaries					
	Printing					
	INSURANCE					
	LOCAL PORT CHARGES HANDLING					
	Freight Charges CXI/FAN					
	Freight Charges CXI/TRN					
	GRAND TOTAL MATERIAL COST					