

**MINISTRY OF LINE & PHOENIX ISLAND DEVELOPMENT
CIVIL ENGINEERING & TECHNICAL DIVISION
TERAINA HOUSING PROJECT**

SUPPLIER _____
CONTACT _____
ADDRESS _____

EMAIL ADDRESS _____
PHONE # _____
DATE _____

INSTRUCTION:

State the company name with all required information above Fill in the material price and in the highlighted column
Double check the quote prior submission, Cotact this email address for further enquiries : civilandtechnical@mlpid.gov.ki

Serial No	Description	Qty	Unit	U/Price	Total
1.0	CONCRETE WORK				
1.01	Portland Cement 40Kg	184	bags		
2.0	REINFORCEMENT WORK				
2.01	Reinforced rod D12mm Ø minimum Grade 300MPa	67	lengths		
2.02	R6 diam bar for stirrups minimum Grade 300MPa	31	lengths		
2.03	665 BRC Mesh reinforcement 6mx2.4m minimum Grade 300MPa	8	sheets		
2.04	Polythene black plastic 1.8x60mx4mm	2.0	roll		
2.05	Tie/Bind Wire (20m length)	9	spools		
3.0	CARPENTRY, FORMWORK & CONSTRUCTION BOX				
3.01	Radiata Pine 100x50mmx6m	35	length		
3.02	Radiata Pine 50x50mmx6m	20.00	length		
3.03	Radiata Pine 200x25mmx6m	2.00	length		
3.04	Radiata Pine 150x25mmx6m	18	length		
3.05	Radiata Pine 75x50mmx6m	105	length		
3.06	Radiata Pine 50x50mmx6m	36	length		
3.07	Formply 2.4mx1.2mx20mm	12.00	sheets		
3.08	Cons Ply 2.4x1.2mx6mm	13	sheets		
3.09	Construction Plywood 2.4x1.2x12mm	9	sheets		
3.10	Cement Board 8mmx1.2x2.4m	44	sheets		
3.11	Bolts M12@150mm long	33	Nos		
3.12	T-Hinges 6"	2	Nos		
3.13	Hasp & Staple 6"	1	Nos		
3.14	Padlock	1	Nos		
3.15	Builder Strapping (25mmx27m)	1	spool		
3.16	Masonry mason's Line braided nylon yellow (500m)	1.00	spools		
3.17	Wood Screws, #10 x 3-1/2",	100.00	nos		
3.18	Smoke detector	1	nos		
3.19	Fire distinguisher	1	nos		
4.0	ROOFING COVERING				
4.01	Roof Sheet 15ft length	27	sheets		
4.02	Standard Ridge cap 2.4m length	5	sheets		
4.03	Standard Flashing edge 2.4m length	8	sheets		
5.0	JOINERY				
5.01	Security mesh window 2x1.2m	7	sheets		
5.02	Fly insect screen 30x0.912m	1	roll		
5.03	Panel door 2040x.849mm	2	no		
5.04	Flush door 2040x.849mm	2	no		
5.05	Butt hinges 100x75mm	7	pairs		
5.06	Entrance Lock set	4	no		
5.07	DPC Tape 200 wide x 15m	1	roll		
5.08	Louver frame 8 blade with screws	12	pairs		
5.09	Louver frame 4 blade with screws	4	pairs		

	5.10	Louvre glass clear 152x710mm	101	nos		
	5.11	Louvre glass Obscured 152x510mm	6	no		
6.0		TILING WORK				
	6.01	Vinyl tile 300x300mm	402	tiles		
	6.02	Vinyl Adhesive 4ltr tin	4	tins		
	6.03	Ceremic tile 150x150	520	tiles		
	6.04	Ceramic tile 300x300mm	71	tiles		
	6.05	Ceremic adhesive 20kg	6	bag		
	6.06	Grout 20kg	2	bag		
	6.07	Spacer	1	pkt		
7.0		PAINTING WORK				
	7.01	Pink Primer paint 4ltr	24	tins		
	7.02	Arcylic primer undercoat 10ltrs-white	3	bucket		
	7.03	Marine Enamel coat paint 4ltr/C-White	22	tins		
	7.03	Enamel coat paint 4ltr/C-light blue	1	tins		
	7.03	Enamel coat paint 4ltr/C- blue	1	tins		
	7.04	Enamel coat paint 4ltr/C- red	1	tins		
	7.04	Enamel coat paint 4ltr/C-yellow	1	tins		
	7.05	Enamel coat paint 4ltr/C-green	1	tins		
	7.05	Enamel coat paint 4ltr/C-black	1	tins		
	7.06	roller brush & tray	1	nos		
	7.06	Skin for roller brush	6	nos		
	7.07	Brushe 100mm	6	nos		
8.0		NAILING WORK				
	8.01	Galvanise Nail 4"	50	kg		
	8.02	Galvanise Nail 3"	40	kg		
	8.03	Galvanised Nail 2"	5	kg		
	8.04	Clout nail 1 1/2"	18	kg		
	8.05	Clout nail 2 1/2"	10	kg		
	8.05	Concrete Nail 2"	1	kg		
	8.06	Concrete Nail 3"	1	kg		
	8.07	Concrete Nail 4"	1	kg		
	8.08	U-nail 1-1/2"	2	kg		
	8.09	Roofing nail 3"	10	kg		
9.0		ELECTRICAL WORK				
	9.01	Switchboard 6 ways	1	unit		
	9.02	Circuit breaker 20a	1	pcs		
	9.03	Circuit breaker 16a	2	pcs		
	9.04	Circuit breaker 6a	1	pcs		
	9.05	Earth wire 6mm ²	10	mtrs		
	9.06	Earth rod 1.5m	1	length		
	9.07	Hose clip 25mm	1	pc		
	9.08	LED fitting 4ft	5	pcs		
	9.09	LEDTube 4ft	5	pcs		
	9.10	Mounting block	8	pcs		
	9.11	Single switch	4	pcs		
	9.12	Double power point	4	pcs		
	9.13	Wood screw 1-1/2"	20	pcs		
	9.14	Cable 1.5mm ²	40	mtrs		
	9.15	Cable 2.5mm ²	40	mtrs		
	9.16	Cable clip #3	3	pkts		
	9.17	Conduit pipe 20mm	6	length		

10.0	PLUMBING WORK			
10.01	<u>Guttering</u>			
10.02	Guttering 150x85-2.5m	10	pcs	
10.03	Gutter brackets (specified gutter)	34	pcs	
10.04	Pvc Waste pipe 100mm	2	lens	
10.05	Waste tee 100mm	1	pcs	
10.06	Waste elbow 100mm	8	pcs	
10.07	Straps 6ft	4	pcs	
10.08	Silicon & kit white	2	pcs	
10.09	Pop revit 3.2x9.6	1	pkts	
10.10	Wood screw 40mm	2	pkt	
10.11	Clout nail flat head	1	kg	
10.12	Roofing(rubber sealer)	1	kg	
10.13	<u>Rainwater Tank</u>			
10.14	Rainwater tank 5000 ltr	1	pcs	
10.15	Elbow 20mm	2	pcs	
10.16	Reducer 20mm by 15mm	1	pcs	
10.17	Gate valve 20mm	1	pcs	
10.18	Male adaptor 20mm	1	pcs	
10.19	Union 20mm	1	pcs	
10.20	PVC pipe 20mm	2	pcs	
10.21	PVC pipe 15mm	1	pcs	
10.22	Solvent Cement 500mls	1	can	
10.23	Thread tape	1	pcs	
10.24	<u>Water site</u>			
10.25	Overhead tank 20mm outlet(500 ltr)	1	pcs	
10.26	Gate valve 20mm	1	pcs	
10.27	Male adaptor 20mm	2	pcs	
10.28	Elbow 20mm	7	pcs	
10.29	Tee 20mm	3	pcs	
10.30	Reducing push 20x15mm	4	pcs	
10.31	Tee 15mm	2	pcs	
10.32	Elbow 15mm	10	pcs	
10.33	Gate valve 15mm	2	pcs	
10.34	Male adaptor 15mm	8	pcs	
10.35	Flexi hose 15mm	2	pcs	
10.36	Shower rose 15mm	1	pcs	
10.37	Female adaptor 15mm	2	pcs	
10.38	Bib tap 15mm	2	pcs	
10.39	PVC pipe 20mm	2	lens	
10.40	PVC pipe 15mm	2	lens	
10.41	Solvent Cement 500mls	1	can	
10.42	PVC Cleaner(Primer) 500mls	1	can	
10.43	Thread tape	4.0	pcs	
10.44	Pipe clip	10	pcs	
10.45	<u>Sanitation side</u>			
10.46	Couple WC P-trap 100mm	1	set	
10.47	Pan connector 100mm	1	pcs	
10.48	Pan seat 100mm	1	pcs	
10.49	Square junction 100mm	4	pcs	
10.50	Waste elbow 100mm 90 degrees	4	pcs	
10.51	Reducing push 100x50mm	3	pcs	
10.52	Vent cowl 50mm	1	pcs	
10.53	Floor grate 50mm	2	pcs	
10.54	Male adaptor 50mm	2	pcs	
10.55	PVC pipe 100mm	3	lens	
10.56	PVC pipe 50mm	1	lens	

11.0	TOOLS & EQUIPMENT					
	11.01	Shovel	5	Nos		
	11.02	Spade	1	Nos		
	11.03	Clawbar	1	Nos		
	11.04	Rake	1	Nos		
	11.05	Generator	1	Nos		
	11.06	Leadwire (freight & hanging)	2	Nos		
	11.07	Power board	2	Nos		
	11.08	Circular Saw	1	Nos		
	11.09	Drop cut saw	1	Nos		
	11.1	Hammer	3	Nos		
	11.11	Hand Saw (Cross cut saw)	1	Nos		
	11.12	Grinder	1	Nos		
	11.13	Drill	1	Nos		
	11.14	Drill bit	2	Nos		
	11.15	Tin snip	1	Nos		
	11.16	Slendge hammer	1	Nos		
	11.17	Scaffolding	2	Nos		
	11.18	Circular saw blade	1	Nos		
	11.19	Grinding blade (block)	2	Nos		
	11.2	Wheel barrow	3	Nos		
	11.21	Tape measure 10m	2	Nos		
	11.22	Measuring tape roll	1	Nos		
	11.23	Bolt cutter	1	Nos		
	11.24	Empty drum 200ltrs	3	Drum		
	11.25	Benzime drum 200ltrs	1	Drum		
	11.26	Diesel drum 200ltrs	1	Drum		
		TOTAL MATERIALS COST				
12.0	SHIPMENT COSTS					
	12.01	INSURANCE				
	12.02	Freight to Tarawa/CIX To Teraina				
	12.03	Handling to Tarawa/CIX To Teraina				
		GRAND TOTAL MATERIAL COST				